

# 数 量 総 括 表

## Bゾーン緑道

工 種	種 別	細 目	規 格	単 位	数 量	摘 要
土 工						
		切 土		m3	235.4	
		路 体 盛 土	W<2.5m	m3	24.9	流用土
		床 掘		m3	57.1	
		埋 戻	W<1.0	m3	0.3	<del>流用土</del>
			1.0≦W<4.0	m3	43.8	<del>流用土</del>
		残 土		m3	292.8.1	
		基 面 整 正		m2	83.0	
	法面整形工					
		切 土		m2	0.0	
		盛 土		m2	39.8	
法 面 工						
	盛 土	種 子 散 布		m2	39.8	
排 水 工						
	側 溝 工					
		U 型 側 溝	US1-1100×600	m	1.3	
		芝 側 溝	B800	m	178.4	
	暗 渠 工					
		管 渠	VUφ300	m	0.9	
	集 水 桝 工					
		集 水 桝	B800-L800-H1400-1	箇所	1.0	
			B1400-L1400-H1100-1	箇所	1.0	
			B1500-L1500-H1100-1	箇所	1.0	
舗 装 工						
	④ < 洗い出しCo <del>2</del> A舗装 >					
	表 層	洗い出しコンクリート	t=10cm	m2	712.6	
	路 盤	再生砕石 (RC-40)	t=15 <del>10</del> cm	m2	680.0	
	凍上抑制層	再生砕石 (RC-40)	t=3 <del>11</del> cm	m2	672.7	
仮 設 工						
	交 通 管 理 工	交通誘導員B		人	210.0	
		JR近接工事管理者		人	7.0	
		列車見張り員		人	7.0	

## 集 計 表

Bゾーン緑道

[illegible]

# 作業土工

作業土工名称		実数量					
		床掘	埋戻			残土	基面整正
			4.0m $\leq$ W	1.0 $\leq$ W<4.0	W<1.0		
		m3	m3	m3	m3	m3	m2
土工							
排水工		57.1		43.8	0.3	<del>13.0</del>	83.0
合計(地山)		57.1	0.0	43.8	0.3	<del>13.0</del>	83.0
合計(補正後)		57.1	0.0	43.8	0.3	<del>8.1</del>	83.0

※残土=床掘-埋戻/0.9(土砂)



[illegible]

Bゾーン

[illegible]

法 面 工 集 計 表

Bゾーン緑道

[illegible]

Bゾーン

- 1-231 -

排水工集計表

## Bゾーン緑道

[illegible]



# 作業土工

作業土工名称		単位	数量	単位数量						実数量					
				床掘	埋戻			残土	基面整正	床掘	埋戻			残土	基面整正
					W<1.0	1.0≦W<4.0	4.0≦W				W<1.0	1.0≦W<4.0	4.0≦W		
U 型 側 溝	US1-1100×600	m	1.3	-	-	-	-	m <sup>3</sup>	m <sup>2</sup>	m <sup>3</sup>	-	-	m <sup>3</sup>	m <sup>3</sup>	m <sup>2</sup>
芝側溝	B800	m	178.4	-	-	-	-	-	4.00	-	-	-	-	-	71.36
管 渠	VUφ300	m	0.9	6.7	3.0	-	-	0.3	7.18	0.6	0.3	-	-	0.3	0.62
集 水 枒	B800-L800-H1400-1	箇所	1.0	17.9	-	15.3	-	-	1.69	17.9	-	15.3	-	2.6	1.69
	B1400-L1400-H1100-1	箇所	1.0	18.8	-	14.0	-	-	3.61	18.8	-	14.0	-	4.8	3.61
	B1500-L1500-H1100-1	箇所	1.0	19.8	-	14.5	-	-	4.00	19.8	-	14.5	-	5.3	4.00

US1-1100×600

延長調書

番号	始 点	終 点	延 長	規 格	摘 要
L	NO. 4 + 19.60		1.30		
合 計			1.30		

## 延 長 調 書

- 1-237 -

VUφ300

延長調書

番号	始 点	終 点	延 長	規 格	摘 要
L	NO. 4 + 19.64		0.30		第1号
L	NO. 5 + 11.92		0.30		第2号
L	NO. 8 + 17.64		0.27		第3号
合 計			0.87		

SM-B800-L800-H1400-1 箇 所 調 書

番号	始 点	終 点	箇 所	規 格	摘 要
L	NO. 8 + 17.64		1		第3号
合 計			1		

SM-B1400-L1400-H1100-1 箇 所 調 書

番号	始 点	終 点	箇 所	規 格	摘 要
L	NO. 4 + 19.64		1		第1号
合 計			1		

## SM-B1500-L1500-H1100-1 箇 所 調 書

番号	始 点	終 点	箇 所	規 格	摘 要
L	NO. 5 + 11.92		1		第2号
合 計			1		

鋪 裝 工 集 計 表

Bゾーン緑道

[illegible]



# 舗 装 工

# 数量計算書

Bゾーン緑道

<p>歩 道 舗 装</p> <p>洗い出しコンクリート舗装</p> <p>④</p> <p><del>②</del> A</p>	<p>表層</p> <p>A= 舗装平面図より =</p> <p>712.62 m2</p> <p>路盤</p> <p>A= 表層と同じ = 712.62</p> <p>張り出し部</p> <p>A= 0.100 × 178.38 = 17.80</p> <p>雨水幹線部</p> <p>A= 1.260 × 40.00 = -50.40</p> <p>Σ A= 680.02 m2</p> <p>凍上抑制層</p> <p>A= 表層と同じ = 712.62</p> <p>張り出し部</p> <p>A= 0.200 × 178.38 = 35.70</p> <p>雨水幹線部</p> <p>A= 1.260 × 60.00 = -75.60</p> <p>Σ A= 672.72 m2</p>	<p>712.62 m2</p> <p>680.02 m2</p> <p>672.72 m2</p>
-------------------------------------------------------------------	-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	----------------------------------------------------