

令和8年度

市道弁天1号線ほか3路線舗装補修工事

当初

数量計算書

上 山 市

上段:当初 下段:変更

[illegible]

数量計算書

○舗装工

測点 (起点側)	起点からの 延長(m)	幅員 (m)	測点 (終点側)	延長 (m)	平均幅員 (m)	面積 (m2)
市道弁天1号線(a)						
No.0	0	4.96	No.1	20.0	4.96	99.1
No.1	20	4.95	No.2	20.0	5.00	99.9
No.2	40	5.04	No.3	20.0	4.91	98.2
No.3	60	4.78	No.4	20.0	4.88	97.5
No.4	80	4.97	No.4+6.5m	6.5	4.97	32.3
No.4+6.5m	86	4.97				
市道弁天1号線(b)						
No.0	0	11.20	No.1	20.0	8.11	162.2
No.1	20	5.02	No.2	20.0	5.02	100.4
No.2	40	5.02	No.3	20.0	5.10	101.9
No.3	60	5.17	No.4	20.0	5.07	101.3
No.4	80	4.96	No.5	20.0	5.00	100.0
No.5	100	5.04	No.6	20.0	5.02	100.4
No.6	120	5.00	No.7	20.0	5.02	100.3
No.7	140	5.03	No.8	20.0	5.06	101.1
No.8	160	5.08	No.8+15.5m	15.5	8.71	134.7
No.8+15.5m	175	12.34				
市道弁天2号線						
No.0	0.0	4.90	No.1	20.0	4.94	98.8
No.1	20.0	4.98	No.2	20.0	4.97	99.4
No.2	40.0	4.96	No.2+17m	17.0	8.67	147.3
No.2+17m	57.0	12.37				
市道弁天3号線						
No.0	0.0	4.63	No.1	20.0	3.71	74.2
No.1	20.0	2.79	No.2	20.0	2.80	56.0
No.2	40.0	2.81	No.3	20.0	2.85	57.0
No.3	60.0	2.89	No.4	20.0	2.94	58.7
No.4	80.0	2.98	No.4+9.3m	9.3	2.96	27.5
No.4+9.3m	89.3	2.93				

市道弁天4号線						
No.0	0.0	5.47	No.1	20.0	4.22	84.3
No.1	20.0	2.96	No.2	20.0	2.98	59.6
No.2	40.0	3.00	No.3	20.0	2.98	59.5
No.3	60.0	2.95	No.4	20.0	3.02	60.3
No.4	80.0	3.08	No.4+8.5m	8.5	3.07	26.1
No.4+8.5m	88.5	3.06	No.4+12m	0.0	5.56	0.0
No.4+12m	88.5	8.05	No.5	8.0	5.72	45.8
No.5	96.5	3.38	No.6	20.0	3.13	62.5
No.6	116.5	2.87	No.7	20.0	2.97	59.4
No.7	136.5	3.07	No.7+7.9m	7.9	3.21	25.3
No.7+7.9m	144.4	3.34				
合計				552.7		2531.0
平均		4.89				

○舗装版破碎

2531.0 m2

○舗装殻

2531.0 × 0.05 = 126.6 m3

○舗装切断

市道弁天1号線(a)No.0	4.96	市道弁天1号線(a)No.4+6.5m	4.97
市道弁天1号線(b)No.0	11.20	市道弁天2号線No.0	4.90
市道弁天3号線No.0	4.63	市道弁天3号線No.4+9.3m	2.93
市道弁天4号線No.0	5.47	市道弁天4号線No.7+7.9m	3.34

計 42.40 m